

OFFICE OF THE CHIEF DISTRICT MEDICAL & PUBLIC HEALTH OFFICER,  
CUTTACK

District Programme Management Unit, N.H.M Cuttack

Letter No- 6623

IDT- 18/05/2018

**Tender Call Notice**

Sealed percentage tender are invited from Registered C/D Class Contractor of state Govt. Registered with Central Govt./MES/Railways/CPWD in Composite manner for execution of work on production of definite proof as licence copy, GST registration certificate, PAN & work Certificate etc. from the appropriate authority for the works in NHM contract form. Further Details are available at CDMO office, Zilla Swastya Bhaban, Cuttack & website [http://ordistricts.nic.in/district\\_home.php](http://ordistricts.nic.in/district_home.php) "District Portal Cuttack.


Sl. No	Name of the work	Location	Amount put to tender(Rs)	EMD to deposit 1%	Cost of tender paper	Class of contractor	Time of completion
1.	Establishment of SNCU at Athagarh SDH, Cuttack.	SDH Athagarh	892232.00	8922.00	4000.00	C&D	2 months
2.	Repair & Renovation work of Dialysis Room at CHC Narsinghpur, Cuttack	CHC Narsinghpur	660893.00	6609.00	4000.00	C&D	2 months
3.	Construction of R.O Plant At CHC Narsinghpur, Cuttack	CHC Narsinghpur	302344.00	3023.00	2000.00	C&D	2 months

Place & Date of selling Tender paper: - Civil wing, DPMU, N.H.M, Cuttack from 21<sup>st</sup> May 2018 to 28<sup>th</sup> May 2018 ( Office hours from 10:30 am to 5.00 pm except holidays).

Place & Date of receipt of Tender paper:-CDMO, Cuttack in tender Boxes installed from 22<sup>nd</sup> May 2018 to 01<sup>st</sup> June 2018 within office hour (10.30to 5:00 pm).

Place & Date of opening Tender: - CDMO, Cuttack on 04<sup>th</sup> June.2018 from 11:00 onwards.

The undersigned reserves the right to reject any on all of the tenderers without assigning any reason there.

  
Chief District Medical  
& Public Health Officer,  
Cuttack.

**BOQ**

<b>Name of the Work:- "Repair &amp; Renovation Work of Dialysis Room at CHC Narsinghpur of Cuttack District".</b>					
<b>Sl No.</b>	<b>Item of work</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
1	Dismantling and removing 2.5 cm. thick grading concrete from roof slab cleaning the surface lowering and removing debris within 50 mt. lead with all labour	0.22	Cum	778.79	171.00
2	Dismantling and removing 2.5 cm. thick grading concrete from roof slab cleaning the surface lowering and removing debris within 50 mt. lead with all labour	320.00	Cum	59.99	19197.00
3	2.5 cm thick grading concrete ( 1:2:2 ) on roof slab with 6mm size h.g.chips laid to proper slope hoisting lowering compacting watering curing with cost carriage	320.00	Cum	258.38	82682.00
4	Providing 20mm thick cement plaster ( 1:4) grading plaster over roof slab laid to proper slope watering curing cost carriage royalty of all materials etc.complete.	320.00	Cum	175.31	56099.00
5	Providing 6mm thick cement plaster ( 1:4) to R.C.C. surfaces finished smooth including closed chipping and slurry treatment watering curing cost carriage royalty of	223.54	Cum	112.02	25041.00
6	R.C.C. ( 1:1½:3 ) with 12cm size h.g. chips including hoisting lowering laying in layers 15 cm thick compacting centering shuttering watering curing with	0.22	Sqm	838.69	184.51
7	Supplying fitting and placing uncoated HYSD bar reinforcement as per drawing with all leads and lifts cost conveyance of all materials etc. complete.	0.20	Sqm	6081.04	1216.00
8	Providing fitting & fixing of false ceiling with aluminium anodised section. AR - 2006, P-237/3	85.48	Sqm	1274.28	108925.45
9	Finishing walls surface with Synthetic putty of approve make and finished smooth and even surface to receive painting incuding scaffolding cost conveyance of all	85.48	Sqm	75.95	6492.21
10	Supplying fitting fixing of aluminium door openable door using OEL anodized Al. door section of 9202 as vertical member, 9201 as top member and 9200 as	25.20	Sqm	5548.10	139812.12
11	Supplying fitting and fixing up window ( sliding type ) made of aluminium section 151-154 ,151-155as window frame section no.151-155 as shutter frame wuth 5 mm	15.55	Cum	4885.90	75975.75
12	Fixing vertified tiles of 600 x 600mm in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 jointed with neat cement slury mixed with pigment	20.00	Cum	1295.46	25909.20
13	Supplying fitting fixing M.S.Door and window shutter with M.S. grill & M.S. choukath including cost of all materials labour T&P etc complete as per direction of the EIC.	74.25	Kg.	67.20	4989.60
14	Distempering two coat to walls with distemper of approved shase to give an even shase including cost conveyance of all materials labour T & P etc. complete.	780.36	Sqm	90.11	70318.24
15	Finishing wall with weather coat paint two coats over a coat of primer of approved shade to give an even shade including cost conveyance of all materials labour T & P	220.50	Sqm	98.06	21622.23
16	Painting two coats with any enamel paint over a coat of primer to new wood or iron works including cost conveyance of all materials labour T & p etc. complete.	161.98	Sqm	137.41	22257.67
				<b>Total</b>	<b>660892.98</b>

My/Our \_\_\_\_\_% (both in figure and word Excess over /Less than/Equal to the estimated cost.

**NB:-** The contractor should not write any thing except quoting of %age and in case any thing else regarding tender rate is mentioned. The tender is stricke out which are not applicable.