

OFFICE OF THE CHIEF DISTRICT MEDICAL & PUBLIC HEALTH OFFICER,
CUTTACK

District Programme Management Unit, N.H.M Cuttack

Letter No- 6623

IDT- 18/05/2018

Tender Call Notice

Sealed percentage tender are invited from Registered C/D Class Contractor of state Govt. Registered with Central Govt./MES/Railways/CPWD in Composite manner for execution of work on production of definite proof as licence copy, GST registration certificate, PAN & work Certificate etc. from the appropriate authority for the works in NHM contract form. Further Details are available at CDMO office, Zilla Swastya Bhaban, Cuttack & website http://ordistricts.nic.in/district_home.php "District Portal Cuttack.

| Sl. No | Name of the work | Location | Amount put to tender(Rs) | EMD to deposit 1% | Cost of tender paper | Class of contractor | Time of completion |
|--------|---|-----------------|--------------------------|-------------------|----------------------|---------------------|--------------------|
| 1. | Establishment of SNCU at Athagarh SDH, Cuttack. | SDH Athagarh | 892232.00 | 8922.00 | 4000.00 | C&D | 2 months |
| 2. | Repair & Renovation work of Dialysis Room at CHC Narsinghpur, Cuttack | CHC Narsinghpur | 660893.00 | 6609.00 | 4000.00 | C&D | 2 months |
| 3. | Construction of R.O Plant At CHC Narsinghpur, Cuttack | CHC Narsinghpur | 302344.00 | 3023.00 | 2000.00 | C&D | 2 months |

Place & Date of selling Tender paper: - Civil wing, DPMU, N.H.M, Cuttack from 21st May 2018 to 28th May 2018 (Office hours from 10:30 am to 5.00 pm except holidays).

Place & Date of receipt of Tender paper:-CDMO, Cuttack in tender Boxes installed from 22nd May 2018 to 01st June 2018 within office hour (10.30to 5:00 pm).

Place & Date of opening Tender: - CDMO, Cuttack on 04th June.2018 from 11:00 onwards.

The undersigned reserves the right to reject any on all of the tenderers without assigning any reason there.


Chief District Medical
& Public Health Officer,
Cuttack.

BOQ

| Name of the work-"Construction of R.O Room at CHC Narsighpur of Cuttack District". | | | | | |
|---|--|-------------|-------------|-------------------|---------------------|
| Sl No. | Item of work | Qty. | Unit | Rate (Rs.) | Amount (Rs.) |
| 1 | Earth work in excavation in foundation in all kinds of soil including earth mixed with boulder (except sheet rocks and boulder requiring blasting) with all leads and lifts including | 12.29 | Cum | 127.97 | 1572.75 |
| 2 | Supplying filling in foundation and plinth with sand in layers not exceeding 22.5cm (9") thick including watering and ramming with cost conveyance, royalties, taxes of the | 10.00 | Cum | 269.42 | 2694.20 |
| 3 | Providing Cement Concrete (1:3:6) with 40 mm down graded of crusher broken hard granite stone aggregate of approved quality from approved quarry for cement concrete work | 2.89 | Cum | 4806.44 | 13890.61 |
| 4 | Brick works with fly ash bricks in cement mortar (1:6) in foundation & plinth including splays cutting circular moulding immersing brick under water for 6 hours watering | 2.22 | Cum | 4361.76 | 9683.11 |
| 5 | Brick works with fly ash bricks in cement mortar (1:6) in superstructure including splays cutting circular moulding immersing brick under water for 6 hours watering curing | 4.80 | Cum | 4395.09 | 21096.43 |
| 6 | 12mm thick cement plaster (1:6) for brickwork including cost conveyance and royalty etc complete | 52.31 | Sqm | 105.26 | 5506.15 |
| 7 | 16 mm thick cement plaster in CM (1: 6)with cost of all labour & materials. | 45.99 | Sqm | 147.80 | 6797.32 |
| 8 | Distempering two coat to walls with distemper of approved shade to give an even shade including cost conveyance of all materials labour T & P etc. complete. | 45.99 | Sqm | 90.11 | 4144.16 |
| 9 | Finishing wall with weather coat paint two coats over a coat of primer of approved shade to give an even shade including cost conveyance of all materials labour T & P etc. | 52.31 | Sqm | 98.06 | 5129.52 |
| 10 | R.C.C. (1:1½:3) with 12cm size h.g. chips including hoisting lowering laying in layers 15 cm thick compacting centering shuttering watering curing with cost carriage royalty of all | | | | |
| a | Column base | 2.88 | Cum | 7290.59 | 20996.90 |
| b | Column | 1.37 | Cum | 12355.49 | 16927.02 |
| c | Plinth beam | 0.99 | Cum | 7603.44 | 7527.41 |
| d | Lintel | 0.19 | Cum | 10211.46 | 1940.18 |
| e | Roof slab | 3.13 | Cum | 10552.14 | 33028.20 |
| f | Roof beam | 0.38 | Cum | 12355.49 | 4695.09 |
| 11 | Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification. | 12.21 | Qntl. | 6081.04 | 74249.50 |
| 12 | Supplying, fitting & fixing of approved design of MS grill gate including all complete | 113.40 | Kg. | 67.20 | 7620.48 |
| 13 | Fixing vertified tiles of 600 x 600mm in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 jointed with neat cement slury mixed with pigment to match the | 24.12 | Sqm | 1295.46 | 31246.50 |

| | | | | | |
|----|--|-------|-----|--------------|------------------|
| 14 | Fixing ceramic wall tiles in dado skirting and riser of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles | 21.30 | Sqm | 1031.78 | 21976.91 |
| 15 | 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size h.g.chips laid to proper slope hoisting lowering compacting watering curing with cost carriage royalty etc. | 25.00 | Sqm | 258.38 | 6460.00 |
| 16 | Providing 20mm thick cement plaster (1:4) grading plaster over roof slab laid to proper slope watering curing cost carriage royalty of all materials etc.complete. | 25.00 | Sqm | 175.31 | 4383.00 |
| 17 | Painting two coats with any enamel paint over a coat of primer to new wood or iron works including cost conveyance of all materials labour T & p etc. complete. | 5.67 | Sqm | 137.41 | 779.00 |
| | | | | Total | 302344.43 |

My/Our _____% (both in figure and word Excess over /Less than/Equal to the estimated cost.

NB:- The contractor should not write any thing except quoting of %age and in case any thing else regarding tender rate is mentioned. The tender is stricke out which are not applicable.